

**Scottish Church College**  
1 & 3 Urquhart Square Kolkata -700 006

**Notice for quotation**

**Ref: Tender Estate/SCC /12/2020-21 Dated 17-03-2021**

**Contact:** Mr. Shibnath Bhattacharyya (M- 98362 72199)

Appropriate quotations are invited in sealed cover from eligible bidder's /suppliers/ vendors according to the following specification.

**Items**

**(This Building is a Heritage Building (Category - A or I).**

Sub:Restoration work/structure strengthening,existing veranda floor treatment and allied civil work of existing damaged veranda with fire exit, damaged cast-iron staircase repair, painting work & teacher's toilet block, of Main Building( North Side Of Scottish Church College).

Sl.No	Description of work	Unit	Qty	Rate	Amount(Rs)
<b>A</b>	<b>Civil work of the existing building.(Outside &amp; Inside the existing toilet area).</b>				
1.0	Making Scaffolding with bamboo and proper staging with working platform.	Sqm	24.00		
2.0	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. In ground floor including roof. (a) upto 150 mm. thick.	Cum	1.2		
3.0	Carefully stripping off worn out plaster and proper joins of walls, column etc. upto any height and in any floor.	Sqm	46.45		
4.0	Carefully stripping off worn out ceiling damaged concrete from existing damaged ceiling etc. upto any height and in any floor.	Sqm	8.00		
5.0	Carefully cleaning existing damaged brick joint mortar by wire brush, chisel, etc.	Sqm	46.45		
6.0	Rule pointing to brick work with ruled joints in lime and surki 1:2 mortar including raking out joints and top finishing (1 lime paste/ putty : 2 surki ).	Sqm	46.45		
7.0	Carefully cleaning at coroship steel portion by sand paper, wire brush etc.	Sqm	8.00		
8.0	Steel work, providing new steel member for welding with damaged steel, by weldingmachine, uncaring, at damaged ceiling RCC portion.	L.s	1.00		
9.0	40 mm thick concreting work, with (Non-Shrink Cementitious concrete) at damaged ceiling, column etc.	Sqm	8.00		

10.0	Providing and making hole of 12mm dia & 8-10 inch depth @ .600 mt. distance (to restrict the additional rising damp and allowing of better breathability of the structure).	Rmt	32.00		
11.0	Protective Plaster with lime, sand & Surkhi mortar including rounding off or chamfering corners as directed and excluding scaffolding & staging Admixed with water proof compound & Traditional Admixture as per direction of the Consultant.(Main building wall surface).	Sqm	46.45		
12.0	<b>Waterproofing work at Barandha floor, &amp; Asbestos roof area</b>				
a	Waterproofing coating,(with elastomeric-polymer) one coat primer.(Diluted)	Sqm	16.00		
b	Waterproofing coating,(with elastomeric -polymer) one coat polymer with 120 GSM synthetic tissue laying.	Sqm	16.00		
c	Waterproofing coating,(with elastomeric -polymer) one coat polymer coating.(Undiluted), to laying 120 GSM synthetic tissue.	Sqm	16.00		
d	Two coats protection coating with white cement marble dust, and elastomeric - polymer.(1:2:1),(Diluted) to laying 120 GSM synthetic tissue.	Sqm	16.00		
13.0	Providing and fixing with necessary fitting PVC pipe 110 mm dia,	Rmt	16.00		
14.0	Pure lime wash with mixing colour pigment try to existing match, three coats with smoothening the surface.	Sqm	140.00		
<b>B</b>	<b>Inside work, (Existing toilet)</b>				
15.0	Providing and fixing new 9" dia chimney pipe with proper mouth with all necessary fittings.(avg length 10'-00")	L.s	1.00		
16.0	Providing and fixing new tiles with tiles adiship mortar at Teacher's canteen.	L.s	1.00		
17.0	M.S angle work at water tank area with proper epoxy painting work complete.	L.s	1.00		
18.0	Providing and applying one coat of wood primer and two coats of Gloss enamel painting work, with smoothening the surface.(ICI/Berger).	Sqm	10.00		
19.0	Providing and applying one coat Acrylic plastic primer and two coats Interior Acrylic plastic base painting work, with smoothening the surface.(ICI/Berger)	Sqm	14.40		
<b>C</b>	<b>Repair work of existing damaged cast iron staircase,(Fire exit)</b>				
20.0	Providing and fixing with M.S angle, flat pati, etc fitting by special electro welding rod and painting work complete.(Only for strengthening, but not beatification).	L.s	1.00		

21.0	Removal of rubbish, earth etc. from the working site and disposal of the same beyond the compound, in conformity with the Municipal / Corporation Rules for such disposal, loading into truck and cleaning the site in all respect as per direction of Engineer in charge.	L.S	1.00		
D	Plumbing work				
22.0	Provision for necessary plumbing works to bring out the waste water of kitchen&ladies' toilet from inside basement to outer surface drain	L.S.	1.00		

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from 17/03/21& close on27/03/2021. The Selection /opening will be made at the Principal's office at 1:00 P.M. on31/ 03/2021.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid &bidder .

*K Mukerji*  
Dr. Arpita Mukerji  
Principal

