

Scottish Church College

1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC / 03/2021-22 Dated 10-09-2021

Contact: Shibnath Bhattacharyya (M -9836272199)

Appropriate quotations are invited in sealed cover from eligible bidder's /suppliers/ vendors for urgent repairs to the Watt Pavillion and its surroundings at Baghmari play ground according to the following specification.

Items

Sl. NO.	Description of items	Unit	Quantity	Rate	Amounts(Rs.)	Remarks
(A)1.	Scaffolding with bamboo and proper staging with working platform	Sq.Mt.	450			-----
2	Carefully removing damaged "tarfelt" part by part with the help of scrapper , Chiselete, with removal of debris	Sq.Mt.	122.5			-----
3	Carefully cutting and raking out the damaged concrete (50mm to 75mm thick) (AV) WITH THE HELP OF CHISEL AND mallet, after giving support from bottom , including cleaning debris	Sq.Mt.	122.5			-----
4	Carefully deplastering /removal of damaged and saline effected plaster including cleaning debris	Sq.Mt.	203.50			-----
5	Carefully cleaning damaged brick joint from old mortar through wire brush, chisel and water.	Sq.Mt.	203.50			-----
6	Replastering with cement mortar (1:4) mixing with water proofing compound with curing	Sq.Mt.	203.50			"Cico " Powder may be mixed as per proportionate.
7	Proving 60mm thick (AV) petty stone work on roof with (1:1:5:3) concrete mixing with water proofing compound embedded with 5.5mm M.S. ROUND BAR @25cm c/c in both ways in proper gradient with curing .	Sq.Mt.	122.5			"Latex" may be used in proper proportion.

Madhumajri Mondal
10/9/21
Principal
Scottish Church College
Kolkata

8	New roofing /shade work with "jindal" colour coated (green) galvanised sheets , cutting as per requirement , with all necessary M.S. frame work and fitting with pointed bolt with necessary painting the frame work.	Sq.Mt.	29.00			-----
9	Repairing doors and windows in different portion of the building (as per existing clue)	One item	Whole job			Windows 16 nos , Doors -5 nos.
10	Fixing of different fittings to doors and windows in diffent area of the building i.e. hinges, door bolts, tarbolt othes etc. (as per requirement)	One item	Whole job			As above
11	Fixing of damaged / missing glass panes to the glass winow/doors in different corner of the building (as per requirement) with good quality putty.	One item	Whole job 30 pcs.			-----
12	Carefully fixing M.S.T. section (50 x 50 x 6) M.M. after taking out the old damaged pieces with cutting /wielding as per requirement with proper epoxy base painting complete.After giving support from bottom.	One item	Whole job 10 pcs.			Ceiling at 1 st floor kitchen, staircase room towards 1 st floor etc.
13	Carefully cleaning to corrosive steel portion by emerycloth, wire brush etc. (M.S.T. section at ceiling C.I. drain water pipe)	One Item	Whole job 50 pcs.			M.S.T. section at ceiling of different rooms , C.I. pipe.
14	Providing and painting one coat red oxide metal primer and two coats gloss enamel painting with smoothening surface complete (ICI/Berger)	One Item (as above)	Whole job 50 pcs.			As above
15	Providing and painting with one coat of wood primer and two coats of gloss enamel painting after prèparing base with smoothening surface complete (ICI/Berger)	Sq.mt.	83			Doors and windows in different direction, specially attend East and South side.
16	Providing concrete door chaukat with raking out the	One Item	Whole job 4			Doors at East and South

Madhumajeri Mondal
10/9/21
Principal
Scottish Church College
Kolkata

	damaged wooden pieces.		nos			side.
(B)	Pump Room					
1	Scaffolding with bamboo and proper staging with working platform	Sq. Mt.	37			-----
2	Dismantling the damaged old brick tile roof stacking serviceable materials and removing rubbish.	One item	8.75 sq.mt.			-----
3	Dismantling old damaged floor including cleaning debris	Sq.mt.	6.00			-----
4	Carefully deplastering /removal of damaged and pulverished plaster from interior and exterior walls including cleaning debris	Sq.mt.	58.00			-----
5	Repalstering with cement mortar (1:4) mixing with water proofing compound with curing .	Sq.mt.	58.00			" Cico " powder may be used as per proportionate.
6	New roofing shade work with "jindal" clour coated (green) galvanised sheet , cutting as per requirement , with all necessary M.S. framework and fittings with pointed bolt with necessary painting work to framework.	sq.mt.	8.75			-----
7	Artificial stone flooring with necessary	sq.mt.	6.00			-----
8	Providing M.S. door to the entrance of room including fitting, fixing and painting complete	One item	1 pc whole job (1.5 x 1.00)mt			-----
9	Revival of electric work within pump room in a systematic way with necessary fittings	One Item	Whole job			-----
10	Revival of plumbing work for pump in a systematic way with necessary fitting	One Item	Whole job			-----
C	Trimming of big trees with shifting the branches to outside of the complex as per direction	One Item	Whole job			West and North Side
D	Removal of garbage/debris in different parts of the building and disposal the same	Cumt.	112.95			Do

Madhurarajeri Mandal
Principal
Scottish Church College
Kolkata
10/9/21

	beyond the compound in conformity with the Municipal Corporation rule for such disposal, loading to truck and cleaning site in all respect as directed					
E	Repairing /Reivival of drain (35 mt. Approx.)					
1	Cleaning the thick sludge from the open drain to bring the original floor level of drain with washing complete	Cumt	3.60			West and North Direction
2	Dismantling all types of masonry excepting cement concrete , as per requirement , stacking serviceable materials at site and removing rubbish as directed	Cumt.	1.5			Do
3	Repairing damaged concrete , if any to the floor of drain , with cement concrete (1:2:4) as per requirement, & direction by the engineer .	Cumt	0.18			Do
4	1 st class brick work (1:6) with cement , sand mortar , as per requirement , after checking levelling the drain base, as directed	Cumt	1.87			Do
5	25 M.M. thick cement plaster work (1:4) to the damaged area also to the new brick work (as per requirement)	Sq. mt.	30			Do
6	Net cement punning (3 mm thick) over the new plastered area with proper curing etc.	Sq. mt.	30			Do
Total						

Note:

Specially for the execution of item no: (A) & (E) contractor may be instructed to attend the same in the presence of an Technical Officer , how to attend the roof work , drainage work in Primary state and complete the same in a satisfactory way.

Madhumajori Mandal
 10/9/21
 Principal
 Scottish Church College
 Kolkata

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day (Monday – Friday) between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from 11/9/21 & close on 21/9/21. The Selection /opening will be made at the Principal's office at 1:30 p.m. on 22/9/2021.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

Madhumanjari Mandal

Dr. Madhumanjari Mandal

Principal

Principal
Scottish Church College
Kolkata

10/9/21

