

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Tender Estate/SCC /01 /2023-24 Dated 12-04-2023

Contact: Dr. Susmita Ghosh (Mobile- 98306 09312)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for Civil Work at B.Ed Building according to the following specifications:

Particulars

Sl. No.	Description of Items	Unit	Quantity	Rate	Amount (Rs.)
1	Preparing temporary scaffolding work with bamboo and rope with necessary platform etc.	Sq.mtr	730.82		
2	Carefully deplastering /removal of damaged and saline effected plaster with cleaning brick joints from old Mortar with brush and chisel rods including cleaning debris etc.	Sq.mtr	257		
3	Carefully splicing work (at damaged bearing area of existing ISMB/Wooden beam) with extra steel props support system, providing and fixing new ISMB or ISMC cutting as per requirement wall area with Zinc chrome base painting work complete after cutting wall with placing the ISMB or ISMC and weiding M.S.plate 6 m.m. thick as necessary at damaged portion of Existing RSJ/ISMB bearing area, with placing concrete bed to bottom of new ISMB or ISMC at ground floor	unit	4 nos		
4	Replastering with lime mortar (1:3) in 20 mm to 25 mm thick mixing with water proofing compound with curing complete	Sq.mtr	257		



5	Scraping and cleaning of moss, blisters and old painted flaked area from the interior parts of different rooms carefully through scrapper, sand paper etc. (lime surface)	Sq.mtr	1489.16		
6	Two coats lime wash with best quality lime , mixing with D.D.L. /glue with smoothening surface	Sq.mtr	1489.16		
7	Three coats lime wash with best quality lime , mixing with D.D.L./Glue with smoothening surface (only for newly plastered area)	Sq.mtr	257		
8	Provision for repairing the partly damaged doors and windows to ground floor toilets and also providing Aluminium Sheet to the both sides of doors to staff toilet & students toilet to prevent constant touch of water to wood surface	One Item	Whole job		
9	Proving and placing of new wooden Bargah sec (75x65) M.M. and max length 1.30 mt. by replacing the damaged wooden bargah with cutting nose etc. after proper examination with giving proper props including complete with great care.	Each	30		
10	Providing and painting two coat of synthetic enamel over one coat of primer to the newly wooden bargah with smoothening surface etc .	Sq.mtrs	10.92		
11	Dismantling the floor partly to lift the W.C. for checking the conceal outlet and fixing a new one without concealing system with adding soil pipe and other fittings to prevent any choking with new flooring in a different shade .	One item	Whole Job		



12	Waterproofing the toilets floor at the 1 st floor with Eposy (B-11, AH-713 resign & curing agent) with fine dry sand & matching colour of floor, after cleaning the tile joints with great care	One item	Do		
13	Provision for repairing and changing of plumbing works to all the five toilets at building after proper examining.	One item	Do		
Overall security room at Pre- 1(B.Ed Building side)					
14 (A)	Preparing temporary scaffolding work with bamboo and rope with necessary platform (outside only.	Sq..mtrs	68.4		
B	Raking out the old and damaged tarfelt from the roof and parapet wall with great care.	Sq.mtrs	32.3		
C	Carefully dismantling all types of Masonry expecting cement concrete plain or reinforced	Cumt	0.86		
D	1 st class brickwork with lime sand mortar (1;3.) and curing work complete .	Cumt	0.86		
E	Carefully deplastering/ removal of damaged and saline effected plaster with cleaning Brick joints from old mortar with brush and chisel rods including cleaning debris	Sq mt.	79.86		
F	Making temporary scaffolding with steel props , steel pipes etc staging with working platform (for removal and refitting) inside work of the room part by part with steel prop. , jack, M.S. pipe , M.S. clamp etc.	Sq.ft.	45.3		
G	Providing and placing of wooden bargah (75x65) M.M with maximum length of 1.30 mtrs cutting nose and carefully removing the old damaged bargas (Siliguri Sal) including painting work complete	Each	24		



H	Providing , fitting and fixing of earthen clay tiles in single layer after raking out the old damaged one with the help of lime , surki and sand mortar (1: 1: 1) with sealing the joints (tiles size : 450x300x25 to 30) mm	Sqmt	6.60		
I	Raking out the old damaged lime concrete from roof in an average thickness of 75 M.M. with great care and cleaning the debris	Sqmt	79.68		
J	Replastering with the lime & sand mortar (1:3) in 20 mm to 25 mm thick mixing with water proofing compound with curing complete	Sqmt	79.68		
K	Scraping and cleaning of moss , blisters from old painted area from the exterior parts of building through scrap, sand paper etc.	Sq.mt	34.38		
L	Providing and applying one coat Primer of 10% antifungal solution modified high bond , Anti alkaline, anti efflorescences sealer dulux sealer E100 + Aquatech PTC or equivalent (dilution with water in the ratio of (1:1) , ICI /Berger	Sq mt	34.38		
M.	Providing and applying two coats weather Emulsion Exterior painting work with smoothening the surface ICI/Berger (weather shield)	Sq.mt	68.76		
N	Providing and applying three coats lime wash with best quality lime, mixing with DDL/Glue with smoothening surface (inner area of room)	Sq.mt.	58.50		



O	Supply and laying true to line and level ,Anti skid body , homogeneous and granular vitrified tiles for floor with cement, sand mortar (1:4) and 2M.M thick cement slurry at back of tiles with necessary pointing (Kajaria/NITCO)	Sqmt	13.20		
P	Revival of electric line with necessary casing, wire and fittings with providing points of light , fan, charger point etc. including all.	One item	Whole job		
Q	Provision for fixed aluminium netting in out side (38 m.m. x 38 m.m.) with sliding frostrated glass pane window (in aluminium frame work with dismantling the old windows including all	Sq. Mtr.	1.35		
R	Provision for fixing aluminium doors (in aluminium frame work) with frostrated glass at top and laminated ply at bottom with dismantling the old door including all	Sq. Mtr.	2.04		
S	Carefully cleaning the R.S.J at ceiling with Emery cloth & painting the same with two coats enamel paint including all.	Sq. Mtr.	2.75		
15	Removal of debris from the working site and disposal the same beyond the compound by maintaining Municipal/Corporation rules	One item	Whole job		
Total					

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **13/04/23** & close on **24 /04/2023**. The Selection /opening will be made at the Principal's office at 3:00 P.M. on 25/04/2023

The Authority of the College reserves the right / discretion for selection based , amount, quality of the bid & bidder.

Madhumanjari Mandal
Dr. Madhumanjari Mandal
Principal
Principal
Scottish Church College
Kolkata

12/4/23

