

Scottish Church College
1 & 3 Urquhart Square Kolkata -700 006

Notice for quotation

Ref: Re-Tendering Estate/SCC /08 /2023-24 Dated 25-04-2023

(against Tender No. Estate/SCC/04/2023-24 Dated 10.04.2023)

Contact: Shibnath Bhattacharyya (M- 98362-72199)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for structural repair with refurbishment to staff quarter (Premises no-2) within college campus according to the following specifications:

Sl. No	Description of Items	Unit	Quantity	Rate	Amount (Rs.)
1	Preparing temporary scaffolding work with Bamboo and rope with necessary platform etc.	Sq.mt	767.25		
2	Carefully deplastering /removal of damaged and saline effected plaster with cleaning brick joints from old mortar with brush and chisel rods including cleaning debris etc.	Sqmt	489.05		
3	Carefully dismantling all types old Masonry including cement concrete plain with cleaning debris etc.	Cumt	5.35		
4	Carefully splicing work (at damaged bearing area of Existing ISMB/wooden beam) with extra steel props support system, providing and fixing new ISMB or ISMC cutting as per requirement wall area , with Zinc chrome base painting work complete after cutting wall with placing the ISMB or ISMC and welding M.S. plate 6 m.m. thick as necessary at damaged portion of existing RSJ/ISMB bearing area , with placing concrete bed to the bottom of new ISMB or ISMC at ground floor	Unit	12 nos		
5	Carefully deplastering /Removal of damaged /Saline effected	Sqmt	46.17		



	/loosen ceiling plaster with cleaning the tiles joint from old mortar with mallet and chisel rods including cleaning				
6	Providing and fixing of new earthen clay tiles in single layer with lime surki mortar mixing with traditional materials (1:2) (size: 45x30x2.5 to 3.00) cm after raking out the damaged /saline effected and missing tiles area	Sqmt	23.08(sqmt) 171 nos		
7	Replastering with lime mortar (1:3) in 20 M.M. to 25 M.M. thick mixing with water proofing compound with curing complete	Sqmt	489.05		
8	Replastering to ceiling area with lime surki and sand mortar (1:1:1) in 5 MM to 10 MM thick mixing with traditional materials including curing etc.	Sq.mt	46.17		
9	Provision for gypsum plaster/putty to the affected area & replaster area with great care and complete	SQMT	535.22		
10	Provision for fixing new collapsible gates (East and south) with necessary fitting after dismantling and removing the old , rusted gates including all	Kg	2 nos 325 kg (APP)		
11	Scraping and cleaning of Moss , blister and old painted flanked area from the interior parts of different rooms carefully through scrapper and paper etc.	Sqmt	673.73		
12	Two coats lime wash with best quality lime , mixing with D.D.L./Glue with smoothening surface (for stair case only)	Sqmt	228.83		
13	Provision for new door as per existing clue available at site, with teak wood plank with	unit	2 nos		



	repairing the frame (if any) with necessary				
14	Provision for new window palla (louvered type) as per existing clue available at site with repairing the frame and necessary fittings including all (After thorough checking & requirement at spot)	Unit	3 no		
15	Provision for repairing the damaged partly missing window (louvered type) including fitting & fixing complete (As per requirement at site)	One item	Whole Job		
16	Provision for repairing the damaged glass windows in different rooms with fixing new glass panes and loosened panes to be fixed with putty including all	one item	Whole Job		
17	Supply , fitting and fixing 1 st class ceramic tiles in walls with sand cement mortar (1:3) 15 M.M. thick & 2 M.M. thick cement slurry to the back of tiles including pointing complete (Kajaria /Nitco)	Sqmt	170.60		
18	Supply and laying true to lime and level , anti skid body , homogeneous and granular vitrified tiles for floor in the cement , sand, mortar (1:4) and 2 M.M. thick cement slurry at back of the tiles with necessary pointing (Kajaria/nitco)	Sqmtr	104.74		
19	Revival of electric line with necessary casing (matching to wall paint) wire and fitting with providing points of exhaust fan , geyser and other necessary points at toilet & kitchen and other rooms (as per requirements) with AC points others including all. (Havels wire to be	One item	Whole Job		



	used with other fittings)				
20	Provision for fixing fittings to the toilets with modern fittings i.e. wash basin, urinal/Squatting plate, commode with cistern, exhaust fan geyser and shower with related fittings with necessary plumbing works	Unit	2		
21	Providing for fixing black stone table at Kitchen with necessary sink, exhaust fan, shelves at the bottom of black stone table including plumbing works	Unit	One		
22	Provision for fixed aluminium netting (38MM X 38 MM) with sliding frostrated glass pane ventilator(for aeration purpose)(all are alluminium frame work)	SQMT	20.20		
23	Provision for folded aluminium doors/windows with frostrated glass pane at top and laminated ply to the bottom portion including fitting and fixing complete	Sqmt	26.79		
24	Providing and applying two coats of interior emulsion paint to the inner surface of walls after cleaning dust and dirt with clothes (ICI /Burger) with finishing	Sqmt	673.73		
25	Providing and applying one coat of Acrylic primer with two coats of interior emulsion paint to the inner surface of wall, where repairing attended , after cleaning the surface with finishing)	Sqmt	535.22		
26	Providing and painting two coats synthetic enamel point over wood works with smoothening surface	Sqmt	171.45		
27	Carefully cleaning the M.S.steel work at ceiling and grill with Emery cloth & painting	Sq,mt	164.56		



	the same with two coats enamel paint including all				
28	Removal of debris , earth from working site and disposal the same beyond the compound by maintaining Municipal /Corporation riles	One item	Whole job		
29	Cleaning and washing the old floors through oxalic acid by using coir brush to bring its originality	One item	Whole Job		
Total					

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **26/04/2023** & close on **03/05/2023**. The Selection /opening will be made at the College office at 3:00 P.M. on **04/05/2023**.

The Authority of the College reserves the right / discretion for selection based on experience, amount , quality of the bid & bidder .

Madhumanjari Mandal
 Dr. Madhumanjari Mandal
 Principal
 Principal
 Scottish Church College
 Kolkata

25/4/23

