

## Scottish Church College

1 & 3 Urquhart Square Kolkata -700 006

### Notice for quotation

Ref: Tender Estate/SCC /01/2024-25 Dated 02-04-2024

Contact: Mr. Shibnath Bhattacharyya (M-98362-72199)  
Mr. Monojit Mondal ( M- 9123086001)

Appropriate quotation is invited in sealed cover from eligible bidders' /suppliers/ vendors for Construction / Renovation work at G.Staff Room with the following specifications:

Part –A

### Construction of a ladies toilet to the north side of Scottish Church College

Sl. No.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
1	Carefully dismantling of type of masonry e'e brick railing, pillar , temporary store of sweepers and other as per requirement	One item	Whole job		
2	Earth work in excavation for erection of concrete filter for laying R.C.C. beam on which floor to be laid for proposed toilet.	Cumt.	0.35		
3	Single layer brick flat soling of picked jhama bricks including ramming , dressing to proper level over sand bed with fitting brick joints with sand .	Sq.mt.	0.50		
4	Base Concrete with graded stone ballast ( 40 mm. size including shuttering) in ( 1:3:6) with casing complete	Cumt.	0.05		
5	Hire and labour charges for shuttering with centring and necessary staging up to 4.00 mt using approved slant proof and thick hard wood planks with required bracings for concrete slab, beams and columns ( at ground floor including caring complete)	Sq. mtrs	14.67		
6	Controlled cement concrete (1:2:4) with well graded 20 mm. size stone chips , excluding shuttering and reinforcement in 10 cm their at ground floor including casing complete .	Cumt	1.54		
7	Reinforcement for reinforced cement concrete work in all sorts & structure including distribution bars, strips, binders etc. cutting the requisite length,	kg	125		



	hooking , and bending in correct shape with bending in 16 gauge black annealed wire etc. complete .				
8	Brick work with 1 <sup>st</sup> class Brick Work ( 125 mm thick ) cement / sand mortar (1:4) in foundation , plinth and superstructure with curing complete	Sq. mt.	37.35		
9	Plastering a wall with sand /cement mortar ( 1:4) in 20 mm thick to ground flooring including curing complete	Sq.mt	76.20		
10	Dismantling the old, damaged asbestos sheet roofing from the existing toilet with stacking the serviceable materials and cleaning debris.	Sq.mt.	20.79		
11	Providing new shade through 'Jindal' Colour coated ( blue) galvanised sheet on necessary M.S. Frame work , painting /applying one coat primer and two coats synthetic enamel paint ,with fixing through self tapping area and finally fixing rain water pipe (4" of supreme brand ) for easy draining out of rain water to nearby surface drain.	Sq.mt.	33.79		
12	Flooring with non skid / mat finish ceramic tiles ( 12"x12" ) in proper level on cement /sand bed (1:4) with painting in tile joints matching to surrounding including finishing.	Sq. mt	7.92		
13	Fixing/laying glazed tile to the walls ( 1: 00 mt) all around the inside walls of toilet and passage also with cement/ sand mortar ( 1:4) including finishing complete .	Sq. mt	18.00		
14	Providing and applying one coat primer and two coats emulsion painting to interior walls with smoothening surface (ICI/Berger)	Sq. mt.	24.60		
15	Providing and applying two coats weather emulsion exterior painting work over one coats of primer with smoothening the surface. ICI/Berger	Sq. mt.	27.00		
16	Stretching electric line to the new toilets with necessary point with installation of 2 nos exhaust fan through casing work including all.	One item	Whole job		
17	Provision for fitting of necessary fixtures to toilets with modern fittings i.e. basin, commodes with cistern and other related fittings with squatting plate with necessary plumbing work for	One item	whole job		



	water line , soil pipe , drainage pipe including all.				
18	Provision for shifting the door to the bottom of existing stairs after raking out carefully by cutting brick wall and fixing the same as proposed.	One Item	Whole job		
19	Preparing temporary scaffolding work with bamboo and rope with necessary platform and dismantling after work.	Sq. mtr	36.00		
20	Provision for petty repair to damage garden " JAFRI " with necessary brick work and plaster during the execution	One item	Whole Job		
21	Provision for transplant the tree in a safer place form the execution area (As suggested)	One Item	Whole Job		
22	Removal of debris and other unserviceable materials beyond the compound after completion of work.				
				Total	

Part -B

Refurbishment of existing computer room with shifting of all wooden partition, almirah, wall cabinet at ground floor of Scottish Church College

Sl. No.	Description of Item	Unit	Quantity	Rate	Amount (Rs.)
1	Preparing temporary scaffolding work with Bamboo and rope with necessary platform and dismantling after work	Sq. mtr	83.40		
2	Loosening and shifting of wooden partition wall , all wooden wall cabinet and almirah with great care and Stacking in a safe place for further reuse as suggested / instructed by authority	One item	Whole job		
3	Repair to floor with pointing to hole at floor & tile joints, if any , with complete in all respect .	One item	Whole job		
4	Preparing base to interior wall fittings the holes after raking out the wall cabinet	One item	Whole job		



	with necessary putty and priming .				
5	Covering the computer accessories, tables & others, which will not be shifted, with hessian cloth etc. to prevent dropping & dust, paint etc. during work.	One item	Whole job		
6	Providing and applying two coats emulsion painting to interior wall and false ceiling with smoothening surface etc.	Sq. mtrs	130.80		
7	Repair to existing electric wiring repair if happen during work etc.	One item	Whole job		
				Total	

This quotation is to be addressed to the Principal , Scottish Church College and has to be submitted to the Principal's office in Scottish Church College , at 1 & 3 Urquhart Square , Kolkata – 700 006, on prescribed working day between 11:00 A.M. and 3:00 P.M. The bid / tender may be submitted from **02/04/24** & close on **08/04/24**. The Selection /opening will be made at the Principal's office at **2:00 P.M.** on **09/04/24**.

The Authority of the College reserves the right / discretion for selection based on experience, amount, quality of the bid & bidder.

*Madhuranjari Mandal*  
Dr. Madhuranjari Mandal  
Principal

2/4/24

Principal  
Scottish Church College  
Kolkata

